



**NOTES:**

1. SAMPLE OF BRICK COLOR SHALL BE APPROVED BY THE CITY ENGINEER PRIOR TO CONSTRUCTION. BRICK MANUFACTURED BY MUTUAL MATERIALS, "BURGUNDY-MICA TILE" OR ENDICOTT "MEDIUM IRONSPOT #46" OR APPROVED EQUAL.
2. CONCRETE SHALL BE 3000 PSI MIN. (CL 3000), 3 1/2" SLUMP (MAX.), SMOOTH FINISH, AND EDGES FINISHED WITH 1/4" EDGE UNLESS OTHERWISE NOTED.
3. THE CENTER OF THE PAVER PATTERN SHALL BE THE STREET TREE.
4. EACH TREE SHALL HAVE APPROXIMATELY 144 S.F. OF PAVER AREA (72 S.F. TREEWELL AND 72 S.F. WALKWAY/SIDEWALK).
5. CONCRETE BAND MAY BE DELETED IF PAVERS ABUT A BUILDING.
6. SEE **PAVEMENT RESTORATION/WIDENING AT CURB DETAIL T05-02** WHEN CUTTING EXISTING CURB.
7. SEE **ROOT BARRIER DETAILS T03-22A AND T03-22B** IF A ROOT BARRIER IS REQUIRED BY ENGINEER TO PROTECT THE SIDEWALK.

**PAVER EDGE DETAIL**

REV NO.	DATE	BY	APPR
1	7/14	RAW	MHA
2	3/16	RAW	MHA
3	3/17	RAW	MHA
4	4/18	RAW	MHA
5	2/21	OIS	MHA
6	9/21	RAW	MHA

PUBLIC WORKS - STREETS AND TRANSPORTATION

APPROVED BY: *M.H. Pedulla*  
ENGINEER MANAGER

APPROVED DATE: 9/1/2021



TREE WELL AND PAVER EDGE INSTALLATION	STANDARD PLAN NUMBER T02-03
--	-----------------------------------

I:\CITYPPS\AUTOCAD\STD\_DETAILS\DRAWING\_FILES\T02-03